

Exhibit D:

Itemized Bid Sheet



All bids due to Brady Blasher by 11:59pm on October 12th, 2026 via email at bblasher@pheasantsforever.org

Project Name: Vertin HMA – Perimeter Fence Installation					
Contractor Name:		Contact Name:		Phone #:	
Email:		Address:		City/State/Zip Code:	
Anticipated Start Date:		Anticipated End Date:		Contractor Signature:	
Item #	Item	Unit	Unit Price	Estimated Quantity	Total Price
1	Mobilization	L.S.		1	
<i>Supplies & Installation</i>					
2	H-Brace Corner Assemblies	Each		4	
3	H-Brace End Assemblies	Each		11	
4	Well Pipe or Octagon Posts	Each		25	
5	5.5' Steel T-Posts and Insulators & Wire Clips	Each		523	
6	4-strands of 12.5 Gauge, High Tensile Wire (170,000 lb. min. tensile strength)	Feet		62,800	
7	Hunter Gate 8' Steel Tube	Each		2	
8	16' Steel Tube Gate	Each		4	
<i>Fence Site preparation</i>					
9	Fence Mowing	Feet		15,700	
	Bid Total				